

KOLKATA METROPOLITAN DEVELOPMENT AUTHORITY
WATER & SANITATION SECTOR
OFFICE OF THE EXECUTIVE ENGINEER, DIVISION-IX/SWTP
CHOWDHURY PARA LANE, SERAMPORE, HOOGHLY.

Abridge NIT No. 3T-1/IX/SWTP/2017-18/122, Dated 14.09.2017.

The sealed tender in Prescribed KMDA format is invites by the Executive Engineer, Div-IX/SWTP, Water & Sanitation Sector for the under noted works from competent, reliable, bonafied and resourceful contractors of proven ability, having experience in similar kind of job during last Five years, directly under a Govt./ Semi-Govt./Undertaking organization, who have successfully completed the work of value not less than 50% of this tender amount.

Sl. No.	Name of Work.	Tender No.	Estimated cost	Earnest money	Time of completion	Cost of tender paper
1.	Emergent roof treatment and allied work over reservoir of UGR of TN-9 within Bhadreswar Municipal area under SWTP. Code No. O&M of SWTP – 4.2	EE-IX/T-03 of 2017-2018.	Rs.1,02,183.00	Rs.2,044.00	1 (One) month	Rs.350.00.

Last date & Time of Receiving of Application (in duplicate)

16.10.2017

4-00 P M

B. Das
14/09/17
EXECUTIVE ENGINEER
DIV-IX/SWTP, (DISTRIBUTION)
(W&S. SECTOR), KMDA.

KOLKATA METROPOLITAN DEVELOPMENT AUTHORITY
WATER & SANITATION SECTOR
OFFICE OF THE EXECUTIVE ENGINEER, DIVISION-IX/SWTP
CHOWDHURY PARA LANE, SERAMPORE, HOOGHLY.

No. 3T-1/IX/SWTP/2017-2018/122

Date : 14.09.2017.

NOTICE INVITING TENDER

The **Kolkata Metropolitan Development Authority** invites competent, reliable, bonafied and resourceful contractors of proven ability, having experience in similar kind of job during last Five years, directly under a Govt./Semi-Govt./Undertaking organization. The value of the work should not be less than 1/2nd of this tender amount. Eligible contractors may submit sealed tenders in Single part in a single outer sealed cover super scribing the Tender No. & date of opening for the work.

Sl. No.	Name of work.	Tender No.	Estimated Cost	Earnest money	Time of Completion	Cost of Tender paper
1.	Emergent roof treatment and allied work over reservoir of UGR of TN-9 within Bhadreswar Municipal area under SWTP. Code No. O&M of SWTP – 4.2	EE-IX/T-03 of 2017-2018.	Rs.1,02,183.00	Rs.2,044.00	1 (One) month	Rs.350.00

3) Deposit of Earnest money in other means shall not be accepted.


k) Earnest money is to be deposited by Bankers cheque/draft in favour of **KOLKATA METROPOLITAN DEVELOPMENT AUTHORITY** payable at Kolkata.

ii) Earnest money deposited for one tender shall not be transferred to another tender.

B. S. Das
14/09/17
Executive Engineer
Div - IX / S.W.T.P.
Distribution
K.M.D.A.

Terms and Conditions :

1. After publication of NIT, tenderers should submit their credentials, Valid **I.T., P.T., TRADE LICENCE, PAN CARD No. & G S T Tin No.** etc. After scrutinizing all the documents, a list of eligible applicants will be displayed on the Notice Board. Tenders will be sold to the eligible applicants only.
2. The tenderers may obtain the Tender Documents from the office of the Executive Engineer, Div-IX/SWTP, Administrative Building at Chowdhury Para Lane, Serampore, Hooghly : 712201.
3. The sealed tender are to be submitted in the under mentioned office as following through the tender boxes, provided for the purpose,
 - a) Office of the Executive Engineer, Div-IX/SWTP, KMDA at Chowdhury Para Lane, Serampore, Hooghly : 712201.
 - b) Office of the Superintending Engineer (W & S Sector) , KMDA at Unnayan Bhavan (6th floor), Salt Lake, Kolkata : 700091.
4. The Tender should be on the basis of the schedule of rates enclosed with the tender papers. The contractors are to quote a particular percentage higher or lower than or at par with the schedule of rates.
5. The tender receipt by the Tendering Authority from other locations will be opened at scheduled date and time in the presence of the intending tenderers.
6. The acceptance of the tender will rest the tender inviting authority who does not bind himself to accept the lowest tender and reserves to himself the authority to reject any or all the tenders received without assigning any reason thereof.
7. No mobilization advance will be paid under any Circumstances.


14/09/17
Executive Engineer
Div - IX / S.W.T.P.
K.M.D.A.

8. If any of the above day stipulated at Sl. No. 2 to 8 observes holiday/ abnormality for reasons whatsoever the respective following working days shall be reckonable for the purpose.

Last date of submission of Application	16.10.2017	up to 4-00 P.M.
Last date of Sale of Tender documents	16.10.2017	up to 4-00 P.M.
Last date of submission of Sealed Tender Paper	18.10.2017	up to 4-00 P.M.
Opening of Sealed Tender Papers.	23.10.2017	up to 4-00 P.M.

B. S. S.
14/09/17

EXECUTIVE ENGINEER
DIV-IX/SWTP, (DISTRIBUTION)
(W&S. SECTOR), KMDA.

No. 3T-1/IX/SWTP/2017-2018/122/1(6)

Date : 14.09.2017.

Copy forwarded for information and necessary action to :-

1. Director of Finance (W&S. SECTOR), KMDA.
2. The Chief Engineer (W&S. SECTOR), KMDA.
3. The Superintending Engineer (W&S Sector), KMDA.
4. The Executive Engineer, Div-VI/SWTP, DIV-I, DIV-O&M-1C, DIV- (E/M)/SWTP, KMDA.
5. The P.R.O., KMDA, Unnayan Bhavan, Salt Lake – Requested to publish in KMDA's Notice Board and KMDA's WEBSITE.
6. NOTICE BOARD.

B. S. S.
14/09/17

EXECUTIVE ENGINEER
DIV-IX/SWTP, (DISTRIBUTION)
(W&S. SECTOR), KMDA.

KOLKATA METROPOLITAN DEVELOPMENT AUTHORITY
WATER & SANITATION SECTOR
OFFICE OF THE EXECUTIVE ENGINEER, DIVISION – IX/SWTP (DISTRIBUTION), W&S SECTOR
ADMINISTRATIVE BUILDING, CHOWDHURY PARA LANE, SERAMPORE, HOOGHLY.

S u b : Declaration of EMERGENT TENDER by the Competent Authority

Repair / Rectification of Fault/Damage/Leakage/Installed by SWTP by Primary/Secondary Grid system/other civil structural works at important & strategic locations.

Name of Work : Emergent treatment of damaged roof and allied work over UGR of TN – 9 within Bhadreswar Municipal area under SWTP.

Location : Bhadreswar Municipal area.

As per the report on inspection submitted by the designated departmental technical representative/ representatives

1. Considerable quantities of rain water percolates through the damaged roof and corroding the reinforcements resulting damaging structural stability. Man holes are to be raised and re-affixed and Resetting of tiles in some portion of UGR roof is also required.
2. The roof is to be repaired with Cement concrete mix(1:2:4) on **Emergent basis** otherwise accident may occur which in turn will hamper the normal water supply in the locality.
3. The damage/leakages unless immediately repaired with new Cement concrete mix on **Emergent basis** would probably cause :
 - a) Complete closure of water supply system within the area in and around the area of TN 9.
 - b) Further aggravation of the fault/damage/leakage will surely increase the projected repairing cost.

Under these circumstances, the repair/rectification work should have to be taken up immediately and therefore it is necessary that the works are to be declared as 'EMERGENT TENDER' by the competent authority and undersigned may be executed the work accordingly.

The proposed expenditure which is surmised to be Rs. 1,05,249.00 (including 3% contingency) to be incurred from the budgetary provision under code No. O & M of SWTP – 4.2 is forwarded for your kind approval.

14/9/17

ASSISTANT ENGINEER
DIV. – IX/SWTP(DISTRIBUTION)
W&S SECTOR, K.M.D.A

14/9/17

SUPERINTENDING ENGINEER (W&S SECTOR)
K.M.D.A

14/09/2017

EXECUTIVE ENGINEER
DIV. – IX/SWTP(DISTRIBUTION)
W&S SECTOR, K.M.D.A

14/9/17

CHIEF ENGINEER (W&S SECTOR)
K.M.D.A

KOLKATA METROPOLITAN DEVELOPMENT AUTHORITY
OFFICE OF THE EXECUTIVE ENGINEER, DIVISION – IX/SWTP (DISTRIBUTION), W & S SECTOR
ADMINISTRATIVE BUILDING, CHOWDHURY PARA LANE, SERAMPORE, HOOGHLY.

Inspection Report on S.W.T.P Primary and Secondary Water distribution Grid system/civil structural system of boosting pumping station cum UGR.

1.	Municipal Area	Bhadreswar Municipal area
2.	Fault/Damage/Leakage location in between / at :	Roof over reservoir of boosting pumping station of TN-9.
3.	Report on Inspection	<p>Considerable quantities of rain water percolates through the damaged roof and corroding the reinforcements resulting damaging structural stability. Man holes are to be raised and reattached also. Resetting of tiles in some portion of UGR roof is also required.</p> <p>The roof is to be repaired with Cement concrete mix(1:2:4) on Emergent basis otherwise accident may occur which in turn will hamper the normal water supply in the locality.</p>
4.	Remarks	The work is Emergent in nature

S. K. Bhaumik
 14/9/17
 JUNIOR ENGINEER/J
 DIV. - IX/SWTP (DISTRIBUTION)
 W & S SECTOR, K.M.D.A.
 K.M.D.A.

Assistant Engineer, Sri S.K Bhaumik please arrange to inspect through concerned Junior Engineer and report

S. K. Bhaumik
 14/09/2017
 EXECUTIVE ENGINEER
 DIV. - IX/SWTP (DISTRIBUTION)
 W & S SECTOR, K.M.D.A.
 K.M.D.A.

Junior Engineer/S.O., Sri A.K. Samanta please arrange for an inspection accordingly

A. K. Samanta
 14/9/17

ASSISTANT ENGINEER
 DIV. - IX/SWTP (DISTRIBUTION)
 W & S SECTOR, K.M.D.A.

Assistant Engineer, Sri S.K. Bhaumik

Complied *S. K. Bhaumik*
 14/9/17
 JUNIOR ENGINEER/S.O
 DIV. - IX/SWTP (DISTRIBUTION)
 W & S SECTOR, K.M.D.A.

Forwarded to : The Executive Engineer, Div – IX/SWTP (Distribution) W & S Sector.

S. K. Bhaumik
 14/9/17
 ASSISTANT ENGINEER
 DIV. - IX/SWTP (DISTRIBUTION)
 W & S SECTOR, K.M.D.A.
 Assistant Engineer
 Div. - IX / S.W.T.P.
 Distribution
 K.M.D.A.



KOLKATA METROPOLITAN DEVELOPMENT AUTHORITY
Unnayan Bhavan, Block - A, Sector - II, Salt Lake, Kol. 91
OFFICE OF THE EXECUTIVE ENGINEER, DIVISION - IX/ SWTP (DISTRIBUTION) , W & S SECTOR
ADMINISTRATIVE BUILDING, CHOWDHURY PARA LANE, SERAMPORE, HOOGHLY.

Name of work : Emergent roof treatment and allied work over reservoir of UGR TN – 9 within Bhadreswar Municipal area under SWTP.

Project code No. : O & M of SWTP 4.2

ESTIMATE / SCHEDULE.

Sl. No.	Description of Item.	Quantity. Unit.	Rate /Unit	Amount (Rs.)
1	Taking out carefully Ranigunge pattern tiles from roof stacking seviceable tiles at site and removing rubbish as directed within a lead of 75m. (Payment to be made on the measurement of portion of roof removed) (Ref : PWD(Bldg.) 2014, P-8, I.No.7.)	60.00 Sq. m.	62.00/Sq. m.	3,720.00
2.	Single Brick Flat Soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand. (Ref: PWD (Bldg.) 2014, P-11, I.No.1)	60.00 Sq. m.	374.00/Sq. m.	22,440.00
3.	Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement, if any, in ground floor as per relevant IS codes. a) Pakur Variety. (Ref : - PWD (Bldg.) 2012, P-14, I.No.7.a.)	6.00 Cu. m.	5,852.56/Cu. m.	35,115.35
4.	Hire and labour charges for shuttering with centering and necessary staging up to 4m. Using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams, columns, lintels curved or straight including fitting, fixing and striking out after completion of works. (Up to roof of ground floor). (When the height of a particular floor is more than 4m. the equivalent floor ht. shall be taken as 4m. and extra for works beyond the initial 4m. ht. shall be allowed under 16 (e) for every 4m. or part thereof.) a) 25 mm to 30 mm shuttering without staging in foundation. (Ref: PWD (Bldg.) 2014, P-26, I.No.12.f.)	7.00 Sq. m.	225.00/Sq. m.	1,575.00
5.	Roofing of Ranigunge pattern tiles 1st class quality (excluding supporting frame work) including tying eaves tiles with galvanised wire and pointing all joints with (b).Cement mortar (1:3) (Cement 0.5Kg/Sq. m (Ref: PWD (Bldg.) 2014, P-61, I.No.15.b.)	60 Sq. m.	248.00/Sq. m.	14,880.00

Sl. No.	Description of Item.	Quantity. Unit.	Rate /Unit	Amount (RS)
6.	Filling in foundation or plinth by silver sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity) a) - Do - by fine sand. (Ref: PWD (Bldg.) 2014, P-2, I.No. 4.(B).	15.00 Cu. m.	74,726.00/Cu. m.	1,120,890.00
7.	125 mm. thick brick work with 1st class Bricks in cement mortar (1:4) in ground floor. (Ref: - PWD (Bldg.) 2014, P-31, I.No.29).	12.00 Sq. m.	772.00/Sq. m.	9,264.00
8.	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course,scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over concrete surface]. a) With 4:1 cement mortar. i) 20mm. thick. (Ref: - PWD (Bldg.) 2014, P-151, I.No.2.ii.a.)	20.00 Sq. m.	199.00/Sq. m.	3,980.00
			TOTAL :	1,02,183.25
			SAY :	1,02,183.00

[Signature]
14/9/17
Junior Engineer
Div - IX / S.W.T.P.
Distribution
K.M.D.A.

[Signature]
14/9/17
Assistant Engineer
Div - IX / S.W.T.P.
Distribution
K.M.D.A.

[Signature]
14/09/2017
Executive Engineer
Div - IX / S.W.T.P.
Distribution
K.M.D.A.